SUPPLEMENTAL / BID BULLETIN NO. 05

November 28, 2024

CW-BENGUET-19-2025/LANIPEW SIP

This addendum is being issued to inform all prospective bidders for the above-named contract of the following information:

The Bill of Quantities shall be:

ITEM NO.	DESCRIPTION	QUANTITY	UNIT	TOTAL COST
I	**TEMPORARY WORKS**			
1	Project Billboard	1.00	lot	5,352.78
2	Construction Safety and Health			
a.	Personal Protective Equipment (PPE)	9,094.50	man-days	167,793.53
II.	**DIVERSION WORKS**			
1	Structure Excavation (Rock)	1.30	cu.m	956.90
2	Rubble Masonry	3.12	cu.m	133,749.44
III.	**CANALIZATION**			
1	Clearing and Grubbing	8,074.95	sq.m	198,159.27
2	Proc/Delivery/Hauling/Inst'n of 2.5"Ø HDPE Pipe, SDR 13.5 (Black)	720.00	ln.m	313,200.00
3	Proc/Delivery/Hauling/Inst'n of 1.5"Ø HDPE Pipe, SDR 13.5 (Black)	4,055.00	ln.m	793,239.10
4	Proc/Delivery/Hauling/Inst'n of 1.25"Ø HDPE Pipe, SDR 9 (Black)	1,050.00	ln.m	193,704.00
5	Proc/Delivery/Hauling/Inst'n of 1.25"Ø HDPE Pipe, SDR 13.5 (Black)	2,170.00	ln.m	290,780.00
IV.	**CANAL STRUCTURES**			
1	Proc/Delivery/Hauling/Inst'n of 1/2"Ø Cable Wire (6 x 19 S IWRC - Steel Core)	1,065.00	ln.m	280,510.35
2	Proc/Delivery/Hauling/Inst'n of 1.5"Ø HDPE Pipe, SDR 13.5 (Black)	575.00	ln.m	112,481.50
3	Proc/Delivery/Hauling/Inst'n of 1.25"Ø HDPE Pipe, SDR 9 (Black)	170.00	ln.m	31,361.60
4	Proc/Delivery/Hauling/Inst'n of 1.25"Ø HDPE Pipe, SDR 13.5 (Black)	230.00	ln.m	30,820.00
IV.	**TERMINAL FACILITIES**			
1	Common Structure Excavation	182.70	cu.m	67,240.91

2	Gravel Blanket	5.33	cu.m	142,000.79
3	211 kg/sq.cm Reinforced Concrete	77.13	cu.m	4,352,355.66
V.	**PUMP AND PUMPHOUSE**			
1	Clearing and Grubbing	50.00	sq.m	1,227.00
2	Common Structural Excavation	13.84	cu.m	5,093.67
3	Gravel Blanket	1.36	cu.m	36,232.85
4	211 kg/sq.cm Reinforced Concrete	3.38	cu.m	187,410.42
5	Laying and Plastering of Concrete Hollow Blocks	30.62	sq.m	177,452.39
6	Proc/Delivery/Inst'n of Wooden Structures/Members	190.02	bd.ft	75,059.80
7	Proc/Delivery/Inst'n of Pre-painted Rib Type GI Sheets and Other Finishings/Accessories	19.52	sq.m	26,387.33
8	Proc/Delivery/Inst'n of Steel Door	2.00	units	29,629.98
9	Proc/Delivery/Inst'n of Steel Casement Windows	4.00	units	59,259.96
10	Proc/Delivery/Instl'n of Piston Type Pump with 12 HP Diesel Engine, and Accessories	1.00	unit	140,748.27
11	Proc/Delivery/Instl'n of Piston Type Pump with 16 HP Diesel Engine, and Accessories	1.00	unit	167,628.27
VI	**MISCELLANEOUS MATERIALS AND ACCESSORIES**			
	CABLED/SUSPENDED PIPELINES			
	16 mm RSB x 6m	6.00	pcs	6,090.72
	#12 Tie Wire (35 kgs/roll)	5.00	rolls	34,123.65
	#10 Tie Wire (35 kgs/roll)	5.00	rolls	34,123.65
	#6 Tie Wire (35 kgs/roll)	5.00	rolls	34,123.65
	1/2"Ø Drop Forged Cable Clip	90.00	pcs	18,869.40
	DIVERSION INTAKE			
	2.5"Ø" GI Nipple x 0.60m	1.00	pc	2,159.54
	2.5"Ø GI Ball Valve	1.00	pc	8,259.01
	2.5"Ø" GI Nipple x 0.30m	1.00	pc	952.09
	INTAKE TANK			
	2.0"Ø" GI Nipple x 12" (Drain & Overflow)	8.00	pcs	4,891.12
	2.5"Ø" GI Nipple x 0.30m	2.00	pcs	1,904.18
	2.5"Ø GI Ball Valve	1.00	pc	8,259.01
	2.0"Ø GI Ball Valve	2.00	pcs	7,677.42
	2"Ø" GI 90° Elbow	2.00	pcs	1,076.28

	RESERVOIR TANKS			
	2"Ø Pre-fab Distribution Pipe - 6 outlets (Welded Part)	14.00	sets	110,073.60
	2"Ø GI Drain & Overflow Nipple x 12"	42.00	pcs	24,113.04
	2"Ø GI Ball Valve (Drains)	28.00	pcs	114,085.16
	2"Ø GI 90° Elbow	14.00	pcs	7,533.96
	1.75M - 2"Ø GI Pipe Sch. 40	14.00	pcs	65,598.96
	1/2"Ø GI Ball Valves	84.00	pcs	87,118.92
	1/2"Ø GI Nipple x 6"	84.00	pcs	9,392.88
	Tank Marker (see plan/layout)	14.00	pcs	110,073.60
	Pre-fabricated Steel Ladder (D16mm)	14.00	sets	78,274.56
	JOINTS			
	1.5" Ø PE Coupler	6.00	pcs	6,814.08
	1.25" Ø GI Check Valve	5.00	pcs	10,553.10
	1.25" Ø PE Coupler	5.00	pcs	5,311.50
	1.25" x 1.25" x 1.25"Ø Tee Compression PE Coupler	5.00	pcs	3,669.10
	1.25"Ø GI Ball Valve (or Gate Valve)	5.00	pcs	12,223.45
	2.5" x 2.25" x 2.5"Ø Tee Compression PE Coupler	2.00	pcs	9,260.16
	APPROVED BUDGET FOR THE CONTRACT			***8,836,441.56***

For the guidance and information of all concerned.

FRANK E. FANGED, PhD
BAC Vice-Chairperson